Proposal for RFP-01 - Meridian Rotating Integrity (fictional)

Field	Value
Document ID	PROP-01
Revision	1
Date	2026-10-26
Prepared by	Meridian Rotating Integrity, Bid Manager
Owner node	region_south_operator
Classification	CONFIDENTIAL

1. Our understanding

P-4101A has tripped three times since its July 2026 motor replacement, with run times falling from 16 to 4 days. Spectra with strong 1x and 2x components, iron and silicon in the oil, and the 2019 SP-14 history all point to misalignment, possible soft foot and sand-assisted bearing wear. We will test these hypotheses and look for others, including a bent column shaft and base plate distortion, which could also explain the rising P-4101B vibration.

2. Methodology

Phase	Activities	Duration
1 Desk review	Review shift reports, PROJ-02, RES-01, spectra	1 week
2 Offshore survey	Vibration and ODS on both pumps, laser alignment, soft foot, base plate flatness, intake screen check	8 days offshore
3 Teardown and lab	Teardown of P-4101A, shaft runout, ISO/IEC 17025 metallurgical lab	4 weeks
4 RCA and options	Cause tree, ranked repair options, procedure	2 weeks

3. Team

- Project lead: rotating equipment engineer, 18 years, ISO 18436-2 Cat IV.
- Field engineer: laser alignment specialist, ISO 18436-2 Cat III.
- Metallurgist: chartered engineer, failure analysis lab manager.
- CVs and two references for similar caisson pump RCAs are in Annex A.

4. Schedule

Final report 10 weeks after award, two weeks inside the 12-week limit. Three people offshore for 8 days, within the bed space constraint. P-4101B checks are split into 3-hour windows.

5. Risk and HSE management

Risk	Mitigation
P-4101B fails during survey	Survey P-4101B first, at low load
Weather delays offshore	Two spare days built into phase 2

Risk	Mitigation
Parts damaged in transport	Sealed, labelled transport; photo record

Full offshore HSE plan in Annex B. All site staff hold valid offshore survival certificates.

6. Cost

Item	Cost (USD)
Phase 1	8,000
Phase 2 (offshore)	41,000
Phase 3 (teardown and lab)	27,000
Phase 4 (report)	12,000
Total	88,000

7. Compliance matrix

Requirement	Compliant	Where
M1 HSE plan and certificates	Yes	Section 5, Annex B
M2 Accredited metallurgical lab	Yes	Section 2, phase 3
M3 Report within 12 weeks	Yes	Section 4
M4 Data stays on operator systems	Yes	Annex C data plan
M5 Compliance matrix	Yes	This section