Ultrasonic Wall Thickness Survey - Gas Export Riser R-3, Platform SP-12 (2024)

Field	Value
Document ID	INS-01-PDF
Revision	1
Date	2024-04-22
Prepared by	Daniel Okafor, NDT Inspector
Owner node	sp12_inspection_team
Classification	INTERNAL

1. Scope

This report covers the 2024 ultrasonic thickness (UT) survey of the 20-inch gas export riser R-3 on Platform SP-12, from the topsides tie-in at EL +12.0 m down to EL +2.0 m. The riser is API 5L X65 line pipe with a nominal wall of 22.2 mm and a minimum allowable wall of 17.5 mm. Readings were taken with a calibrated single-element probe through the coating where it was intact, and on bare metal where coating had already failed.

2. Readings

Location	Nominal (mm)	Measured (mm)	Date	Inspector
R-3 EL +12.0 m, 12 o'clock	22.2	21.9	2024-04-16	D. Okafor
R-3 EL +12.0 m, 6 o'clock	22.2	21.7	2024-04-16	D. Okafor
R-3 EL +8.5 m, 3 o'clock	22.2	20.4	2024-04-16	D. Okafor
R-3 EL +8.5 m, 6 o'clock	22.2	20.1	2024-04-16	D. Okafor
R-3 EL +5.0 m, 6 o'clock	22.2	20.9	2024-04-17	M. Rostami
R-3 EL +2.0 m, 6 o'clock	22.2	21.6	2024-04-17	M. Rostami
R-3 clamp C-2, 9 o'clock	22.2	21.8	2024-04-17	M. Rostami

3. Findings

- General wall loss above EL +10 m is below 0.5 mm and consistent with the 2021 baseline.
- Localised wall loss of up to 2.1 mm in the splash zone at EL +8.5 m, south-facing side.
- Coating breakdown (blistering, rust staining) over about 0.6 m2 in the splash zone.
- No defects found at clamp C-2.

4. Recommendation

Repeat the splash zone survey within 24 months and add more clock positions between EL +5 m and EL +9 m. Plan a coating repair for the splash zone at the next suitable weather window.

Fictional test fixture. Region South Gas Operator is not a real company.